

# Status of the NEMO project

*Piera Sapienza on behalf of the NEMO  
collaboration*



Istituto Nazionale di Fisica Nucleare  
Laboratori Nazionali del Sud



NEUTRINO MEDITERRANEAN OBSERVATORY

# Outline

- The NEMO R&D activities: towards an underwater km<sup>3</sup> neutrino telescope
  - Site exploration - Capo Passero site properties
  - Feasibility study and preliminary design of the km<sup>3</sup> detector
- NEMO Phase-1 (2003-2007) @ *the LNS Test Site (2000 m)*
  - Aim of the project and system description
  - Achievements and lessons learned
- NEMO Phase-2 (2005-2008) @ *the Capo Passero Site (3500 m)*
  - Description of the infrastructure
  - Detector prototypes
- Conclusions and perspectives

# The NEMO Collaboration



**INFN**

Bari, Bologna, Catania, Genova, LNF, LNS,  
Napoli, Pisa, Roma

**Universities**

Bari, Bologna, Catania, Genova, Napoli,  
Pisa, Roma "La Sapienza", Pavia CIBRA



**CNR**

Istituto di Oceanografia Fisica, La Spezia  
Istituto di Biologia del Mare, Venezia  
Istituto Sperimentale Talassografico, Messina



**Istituto Nazionale di Geofisica e Vulcanologia (INGV)**



**Istituto Nazionale di Oceanografia e Geofisica Sperimentale (OGS)**



**Istituto Superiore delle Comunicazioni e delle Tecnologie  
dell'Informazione (ISCTI)**




More than 80 researchers from INFN and other italian institutes


# The Capo Passero site

The site was proposed in January 2003 to ApPEC as a candidate for the km<sup>3</sup> installation

- Depths of more than 3500 m are reached at about 100 km distance from the shore
- Water optical properties are the best observed in the studied sites ( $L_a \approx 70$  m @  $\lambda = 440$  nm)
- Optical background from bioluminescence is extremely low
- Stable water characteristics no seasonal variation observed
- Deep sea water currents are low and stable (3 cm/s avg., 10 cm/s peak)
- Wide abyssal plain, far from the shelf break, allows for possible reconfigurations of the detector layout




# 3D view of the area





# Optical Water Properties @ Capo Passero

More than 25 campaigns performed. Several joint NEMO-ANTARES campaigns to measure water properties in Capo Passero and Toulon



*Absorption lengths*



➤ **PMT: 10"**

➤ **Thres: ~.5 SPE**

**Fraction of time**

**R > 200 kHz**



Absorption lengths measured in Capo Passero are compatible with optically pure sea water data

The measured value of about 30 kHz is compatible with pure  $^{40}\text{K}$  background

# Feasibility study for the km<sup>3</sup> detector

Reduce the number of structures to reduce the number of underwater connections and allow operation with a ROV


Detector modularity



# Tower detector performance

## Sensitivity

Sensitivity to point-like sources ( $E_\nu^{-2}$  spectrum)




*IceCube simulations from Ahrens et al. Astrop. Phys. 20 (2004)*

NEMO 81 towers 140m spaced - 5832 PMTs  
IceCube 80 strings 125m spaced - 4800 PMTs

**NEMO search bin  $0.3^\circ$**   
**IceCube search bin  $1^\circ$**

## Reconfigurability

Effective areas with different element



	tower spacing	floor spacing
Black line	140 m	40 m
Red square	300 m	60 m
Black points	300 m	40 m

# The NEMO Phase-1 project

- Validation of the technological solution proposed for the realization and installation of the km<sup>3</sup> detector
- Realization of a technological demonstrator including all the key elements of the km<sup>3</sup>
  - *Mechanical structures*
  - *Optical end environmental sensors*
  - *Read out electronics*
  - *Data transmission system*
  - *Power distribution system*
  - *Acoustic positioning system*
  - *Time calibration system*
- Multidisciplinary activities
  - *Ovde (measurements of the acoustic background at 2100 m depth, daulphins and sperm whales)*
  - *SN-1 (first operative node of ESONET)*

# NEMO Phase-1- LNS test site



**Double armored cable**  
2.330 m

**Single armored cable**  
20.595 m


**BU**

**North branch**  
5.220 m



SN-1 recorded a large number of seismic events.

**South branch**  
5.000 m





**Junction Box**

## Cable features


10 optical fibers ITU-T G-652

6 electrical conductors  $\Phi = 4 \text{ mm}^2$

**Frame**



**Jumper 300m**



**Jumper 300m**


**Mini-tower - 4 floors**



# The Junction Box

Data transmission electronics  
Power distribution and control  
system  
Optical fibre splitters  
Innovative design to decouple  
the corrosion and pressure  
resistance problems

*Electronics pressure  
vessels*



**December 2006**


*Preparation to the deployment*



# NEMO Phase-1 installation

**December 10 2006**

*Deployment of the Junction Box*





*Accidental fall on the ship deck during deployment  
JB tested for functionality and deployed*


# NEMO Phase-1 installation

**December 10 2006**

*Deployment of the Junction Box*



# Scheme of the prototype tower



4 floors

*Length 15 m*

*Vertical spacing 40 m*

16 Optical Modules with 10" PMT

Acoustic Positioning

*2 hydrophones per floor*

*1 beacon on the tower base*

Environmental instrumentation

*1 compass + tiltmeter in each Floor*

*Control Module*

*CTD (Conductivity-Temperature-Depth) probe on floor 1*

*C\* (attenuation length meter) on floor 2*

*ADCP (Acoustic Doppler Profiler) (including compass) on floor 4*

# NEMO Phase-1 installation

**December 13 2006**

*Exit from the shore station*



# NEMO Phase-1 installation

**December 13 2003**

*Loading of the tower*



# NEMO Phase-1 installation

**December 15 2003**

*Deployment of the tower*




# NEMO Phase-1 installation

**December 16 2006**

*Connection of the tower to the JB*




# Atmospheric muon reconstruction



January 2007  
Run 23 file 1  
Event 189722  
11 PMT involved

- Trigger local coincidence up-horizontal ( $\Delta t=20\text{ns}$ )
- Aart Reconstruction
- Background rejection  
→ causality with the highest in charge and in coincidence

# Atmospheric muon reconstruction



January 2007  
Run 23 file 1  
Event 356615  
11 PMT involved

- Trigger local coincidence up-horizontal ( $\Delta t=20\text{ns}$ )
- Aart Reconstruction
- Background rejection  
→ causality with the highest in charge and in coincidence

# Lessons learned: the junction box

- Oil bath solution successful
  - Applied to the JB and the electronics containers of the tower
  - All power electronics under pressure in oil bath
- Importance of redundancies
  - All control channels in the JB duplicated
  - Minor failures on some control boards overcome via redundant path

but ...

- Malfunctions due to accidental crash
  - Recovery of the JB (June 16 2007)
  - Repair and redeployment (planned in autumn)

# Lessons learned: the tower

- No water leakage
- Loss of buoyancy
  - Due to deterioration of the buoy material under pressure
  - Addition of an extra buoyancy planned
- Need of thorough tests of each component
- Characteristics of the front-end electronics and data transmission system to be kept in Phase-2 design
  - Acquisition of the signal waveform
  - Remote firmware dynamic loading
  - Low power dissipation (12 W / floor)
  - “Symmetric” on-shore off-shore electronics
- Successful integration of a complex structure, but some choices need to be revised
  - Simplification of the backbone cable
  - Optimization of the floor modules

# NEMO Phase-2: a deep sea station (3500 m)




## INFRASTRUCTURE UNDER CONSTRUCTION

- Shore station in Portopalo di Capo Passero
- 100 km electro optical cable
- Underwater infrastructures

## STATUS AND PLANS

- Electro-optical cable (>50 kW, 20 fibres) delivered and loaded onboard the cable layer vessel
- Cable deployed (summer 2007)
- Power feeding system under construction, acceptance tests december 2007
- Installation of cable termination frame with DC/DC converter beginning 2008
- Renovation of the shore station building under way. Completion beginning 2008
- Tower deployment foreseen for mid 2008



# Modifications and upgrades in NEMO Phase-2

- Full tower with 16 floors (12 meter size)
  - Same electronics of Phase-1, but two floors devoted to R&D (new electronics, directional OMs, ...)
- New DC power system to comply with the feeding system provided by Alcatel
- Optimization of the electronics and data transmission
- Integration of a new acoustic station and new time calibration system

# Conclusions and perspectives

- Overall successful experience of NEMO Phase-1
  - Re-deployment of the Junction Box - autumn 2007
  - Buoyancy
  - Data analysis - in progress
- Changes and upgrades in NEMO Phase-2
  - Simplification of integration procedures
  - cost reduction
- The experience gained will contribute to the advancement of the KM3NeT activities
- NEMO program and time schedule are well fitted to the Design Study and Preparatory Phase (negotiation phase started in these days) of KM3NeT